


OLYMPIC FOUNDRY VB910 VALVE
BOX AND COVER WITH "W"
CAST IN THE TOP SURFACE




PAVEMENT

HAND TAMP BACKFILL
AROUND TOP SECTION

6" TYPE PSM SDR 35 PVC,
D3034 PIPE SPACER,
LENGTH AS NECESSARY


6" MIN.
12" MAX.

OPERATOR EXTENSION
(SEE DETAIL No. 311)




NOTES:

- 1) VALVE BOX NOT TO REST ON OPERATING ASSEMBLY.
- 2) OPERATOR EXTENSION REQUIRED WHEN VALVE NUT IS DEEPER THAN 3 FEET FROM FINISHED GRADE.
- 3) CENTER VALVE BOX ON AXIS OF OPER. NUT.
- 4) PROVIDE 24" SQUARE BY 4" THICK CONCRETE PAD AROUND VALVE BOX OUTSIDE OF PAVED AREAS
- 5) VALVE BOX COVER SHALL BE A MINIMUM OF 4 1/2" IN LENGTH



C:\04\0682\100 General Services\CAD\X-1.dwg Oct/28/05



DATE:	BY:	REVISION

TYPICAL GATE VALVE
SETTING DETAIL

SCALE:	N.T.S
APPVD:	BAB
DATE:	10/05
DWG NO.:	310